AMERICANS WITH DISABILITIES ACT (ADA) TRANSITION PLAN FOR PUBLIC FACILITIES



110 North Main Street Monticello, IN 47960

July 5, 2022

TABLE OF CONTENTS

1.	INTRODUCTION	2
2.	TRANSITION PLAN DEVELOPMENT	3
	A. ADA COORDINATOR	3
	B. GRIEVANCE PROCEDURE	4
	C. SELF-EVALUATION/COMMITMENT/SCHEDULE	5
	D. ADA STANDARDS AND GUIDELINES	5
3.	PUBLIC INVOLVEMENT	6
4.	IMPLEMENTATION	6

APPENDICES

APPENDIX A: COMPLAINT/GRIEVANCE FORM	7
APPENDIX B: BUILDING AND STRUCTURE REVIEW	9
APPENDIX C: SIDEWALK AND CURB RAMPS REVIEW	70

INTRODUCTION

The Americans with Disabilities Act (ADA) was enacted on July 26, 1990, and later amended effective January 1, 2009. As written and implemented, the ADA provides comprehensive civil rights protections to persons with disabilities in the areas of employment, state and local government services, access to public accommodations, transportation, and telecommunication. The ADA is a companion civil rights legislation to the Civil Rights Act of 1964 and Section 504 of the Rehabilitation Act of 1973. To be protected by the ADA, one must have a disability or have a relationship or association with an individual with a disability. An individual with a disability is defined by the ADA as a person who has a physical or mental impairment that substantially limits one or more major life activities, a person who has a history or record of such impairment, or a person who is perceived by others as having such impairment. The ADA, however, does not specifically name all the impairments that are covered. The ADA is divided into five sections covering the following topics:

Title I: Employment

Title II: Public Services (and Transportation)

Title III: Public Accommodations (and Commercial Facilities)

Title IV: Telecommunications

Title V: Miscellaneous Provisions

Title II specifically prohibits state and local governments from discriminating against persons with disabilities or from excluding participation in or denying benefits of programs, services, or activities to persons with disabilities. It is under this title that this transition plan has been prepared. This transition plan is intended to outline the methods by which physical changes should be made to give effect to the non-discrimination policies described in Title II.

TRANSITION PLAN DEVELOPMENT

To ensure program accessibility for people with disability in the community, White County has developed a Transition Plan, which is to be considered good practice.

This Transition Plan for Public Facilities considers the following:

A. ADA COORDINATOR:

Effective communication is essential to address all the complaints or concerns of all individuals. To keep the lines of communication open, and thereby ensure effective communication between all parties, White County has appointed the following person as the ADA Coordinator:

Leah Hull ADA Coordinator PO Box 342/ 110 N Main St Monticello, IN 47960 574-583-4585 Ihull@whitecountyindiana.us

The ADA Coordinator shall coordinate the County's efforts to comply with and carry out its responsibilities under Title II of the ADA, including any investigation of any complaint communicated to the ADA coordinator. Such complaints may take the form of alleging noncompliance with ADA mandates or alleging any actions that would be prohibited under ADA. The County shall make available to all interested individuals the name, office address, and telephone number of the employee(s) so designated and shall adopt and publish procedures for the prompt and equitable resolution of complaints. Every complaint must be directed in writing to the ADA Coordinator.

B. GRIEVANCE PROCEDURE

The grievance procedure established below is intended to adhere to the standards outlined in the ADA. The procedure must be used by anyone who wishes to file a complaint alleging discrimination on the basis of disability in the provisions of services, activities, programs, or benefits provided by White County. The complaint should be in writing and contain information about the alleged discrimination such as name, address, phone number of the complainant and location, date, and description of the problem. An example grievance form can be found in Appendix A of this document. Alternative means of filing complaints, such as personal interviews or recordings of the complainant will be made available for persons with disabilities upon requests. The complaint should be submitted by the grievant and/or his/her designee as soon as possible but no later than 180 calendar days after the alleged violation to the ADA Coordinator at the address shown under 'A. ADA COORDINATOR' on page 3. Within 15 calendar days after receipt of the complaint, the ADA Coordinator or his/her designee will meet with the complainant to discuss the complaint and the possible resolutions. Within 15 calendar days of the meeting, the ADA Coordinator or his/her designee will respond in writing, and where appropriate, in a format accessible to the complainant, such as large print, Braille, or audio tape. The response will explain the position of White County and offer options for substantive resolution of the complaint. If the response by the ADA Coordinator or his/her designee does not satisfactorily resolve the issue, the complainant or his/her designee may appeal the decision within 15 calendar days after receipt of the response to the ADA Coordinator or his/her designee. Within 15 calendar days after receipt of the appeal, the ADA Coordinator or his/her designee will meet again with the complainant to discuss the appeal and possible resolutions. Within 15 calendar days after the meeting, the ADA Coordinator or his/her designee will respond in writing, and, where appropriate, in a format described above that is accessible to the complainant, with a final resolution of the complaint. All written complaints received by the ADA Coordinator or his/her designee, appeals to the ADA Coordinator or his/her designee, and responses from ADA office will be retained by White County for at least three years.

C. SELF-EVALUATION/COMMITMENT/SCHEDULE

HWC Engineering, acting as a representative of White County, has performed a cursory review of all White County properties and structures for ADA compliance. The results of this evaluation of all the White County properties and structures can be found in Appendix B. HWC Engineering, acting as representative of the White County has also performed a review of all sidewalks and curb ramps for ADA compliance. The results of this evaluation will be found in Appendix C.

The County is committed to making sidewalks, curb ramps, public areas and countyowned facilities accessible to all pedestrians including those with disabilities. This will be accomplished through the following programs:

- All new construction, reconstruction, road construction or alterations, including federal projects under the control and/or inspection of White County will be in compliance with all federal, state and local ADA requirements.
- Buildings and municipal-owned structures will be brought into compliance as funds are available. Specific complaints will be prioritized.

D. ADA STANDARDS/GUIDELINES

The standards are intended to apply to all construction undertaken within the County Right-of-Way. For sidewalks within the county right-of-way, the "Proposed Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way" (PROWAG) should be used. For buildings and facilities, the "ADA Accessibility Guidelines for Buildings and Facilities" (ADAAG) along with the ADA accessibility guidelines described in the White County Zoning Control Ordinance should be used.

PUBLIC INVOLVEMENT

On January 24, 2022 the County entered into contract with a consultant to provide a selfevaluation of the public rights-of-way and facilities and an updated ADA Transition Plan. At the June 6, 2022, County Commissioners meeting the consultant presented and discussed the draft ADA Transition Plan including self-evaluation. At that time, the draft document became public record and available for a two-week review and comment period. On July 5, 2022, the consultant presented the final ADA Transition Plan including the self-evaluation and the Commissioners approved it.

IMPLEMENTATION

The County Commissioners approved the ADA Transition Plan in public forum at the July 5, 2022 meeting. Implementation of the plan began on that date. Not only does the County commit to following the guidelines set forth in this Transition Plan but it also commits to actively revising and amending this document as new information is discovered. Further, as a matter of policy, this document will be updated at least every three years. Finally, a copy of this document has been placed on file at the White County Government Building, with the ADA Coordinator.

APPENDIX A: COMPLAINT / GRIEVANCE FORM

Grievant Information:

Grievant Name:					
Address:	City:	State:	Zip Code:		
Phone:	Email:				
Alternative Phone:					

Person Preparing Complaint Relationship to Grievant (if different from Grievant):

Grievant Name:						
Address:	City:	State:	Zip Code:			
Phone:	Email:					
Alternative Phone:						

Please specify any location(s) related to the complaint or grievance (if applicable):

Please provide a complete description of the specific complaint or grievance:

Please state what you think should be done to resolve the complaint or grievance:

Please attach additional pages as needed.

Signature: ______ Date:

Please return to: Leah Hull, ADA Coordinator, PO Box 342/ 110 N Main St; Monticello, IN 47960

Upon request, reasonable accommodation will be provided in completing this form or copies of the form will be provided in alternate formats. Contact the ADA Coordinator at the address listed above or via telephone 574-583-4585

APPENDIX B: BUILDING AND STRUCTURE REVIEW

BUILDING EVALUATION

White County, through its hired consultant, completed a cursory building and structure review. The following sections describe the County's various buildings and ADA facilities.

ADA Requirements (PROWAG & ADAAG)				
Item:	Requirement:			
Parking Stall	96" Min. Width			
Parking Aisle Width	96" Min. Width			
Ramp	48" Min. Width			
Ramp Handrails	34" – 38" Height			
Ramp Slope	1:12 Max. Running Slope			
Kamp Stope	1:48 Max. Cross Slope			
Door Openings	32" Min. Width			
Bathroom Stall Door Opening	32' Min. Width			
Bathroom Stall Dimensions	56" DEEP x 60" WIDE			
Grab Bars	33" - 36" Height			
Urinals	17" Max. Height			
Toilet Seat	17" – 19" Min. Height			
Counter / Sink	34" Max. Height			
Towel Dispenser / Dryer	48" Max. Height, 20" Max. Reach Depth			
Soap Dispenser	48" Max. Height, 20" Max. Reach Depth			
Fountain Spout Outlet	36" Max. Height			

AMERICANS WITH DISABILITIES ACT (ADA) TRANSITION PLAN FOR PUBLIC FACILITIES White County, Indiana

FACILITIES EVALUATED

A.	White County Building - Courthouse	11
B.	White County Building Annex – Solid Waste	23
C.	White County Sheriff's Department/ Jail	29
D.	White County Highway Garage	35
E.	Ivy Tech Community College Monticello	41
F.	White County Health Department	49
G.	White County Airport	55
H.	White County Community Corrections	61
I.	Rental Property – Broadway in Monticello	66

A. WHITE COUNTY BUILDING (COURTHOUSE) 110 N MAIN ST; MONTICELLO



Court Street Curb Ramp




Curb Ramp by Entrance



Curb Ramp NE of Entrance




Courthouse Street Parking



East Front Entrance Ramp



West Front Entrance Ramp



Front Entrance



Front Entrance Inner Door



Basement Water Fountain



First Floor Water Fountain



Second Floor Water Fountain



Third Floor Water Fountain



Basement Unisex Restroom



Basement Unisex Toilet



Basement Unisex Sink



Basement Women's Restroom Sink Area



Basement Women's Restroom Stall



First Floor Restroom Entrances



First Floor Men's Stall



First Floor Men's Sink Area



First Floor Men's Urinals



First Floor Women's Restroom



First Floor Women's Stall



First Floor Women's Sink Area



Third Floor Restrooms




Third Floor Men's Sink Area



Third Floor Men's Urinals



Third Floor Men's Stall



Third Floor Women's Restroom



Third Floor Women's Sink Area



Third Floor Women's Stall



Third Floor Women's Stalls

Summary of Facility

For this study, the roadside parking, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

- Curb Ramp widths are less than ADA requirements and no detectable warnings in the area of the Courthouse. No Compliance issues for White County due to Monticello maintaining sidewalks and parking.
- Unisex Basement Restroom's urinal and toilet seat are taller than requirements and inside passage width is less than requirements.
- Women's Basement Restroom ADA stall door width is smaller than requirements, toilet seat is taller than requirements and inside passage width is less than requirements.
- Men's First Floor Restroom door opening is less than requirements, ADA stall door width is less than requirements, stalls are smaller than requirements, urinal exceeds height requirements, toilet seat is lower than requirements, there are no grab bars in stall and inside passage is less than requirements.
- Women's First Floor Restroom stall door width is smaller than requirements, ADA stall door width is less than requirements, stalls are smaller than requirements, toilet seat is lower than requirements, grab bars in stall are angled and inside passage is less than requirements.
- Men's Third Floor Restroom door opening is less than requirements, ADA stall door width is less than requirements, stalls are smaller than requirements, urinal exceeds height requirements, toilet seat is lower than requirements, there are no grab bars in stall and inside passage is less than requirements.
- Women's Third Floor Restroom ADA stall door width is less than requirements, stalls are smaller than requirements, toilet seat is lower than requirements, there are no grab bars and inside passage is less than requirements.

Courthouse Parking						
Stall Width	Measured	96"				
Stall Width	ADA	96" MIN				
Aiolo \A/idth	Measured	N/A				
Aisle Width	ADA	96" MIN				
Curb Ramp	Measured	40"	44"	144"		
Width	ADA	48" MIN	48" MIN	48" MIN		
Curb Ramp	Measured	0.57%	0.13%	0.38%		
Cross Slope	ADA	2% MAX	2% MAX	2% MAX		
Curb Ramp	Measured	3.90%	7.95%	4.70%		
Running Slope	ADA	8.33% MAX	8.33% MAX	8.33% MAX		
Notes: Street Parking		Ramp located on Court st, main entrance	NW corner of building.	East of main entrance C.R. No detectable warning surface		

Courthouse Building					
Domp Dupping Slope	Measured	4.85%	4.45%		
Ramp Running Slope	ADA	8.33% MAX	8.33% MAX		
Bamp Cross Slope	Measured	0.37%	0.17%		
Ramp Cross Slope	ADA	2% MAX	2% MAX		
Bamp Width	Measured	54"	60"		
Ramp Width	ADA	36" MIN	36" MIN		
Ramp Handrails	Y/N	Y	Y		
	Measured	33"	33"		
Handrail Height	ADA	34" - 38"	34" - 38"		
Front Door	Measured	60"(Outer)	33"(Inner)		
Front Door	ADA	32" MIN	32" MIN		
Fountain Spout Outlat Haight	Measured	45"(basement)	46.5"(1st)	46"(2nd)	46"(3rd)
Fountain Spout Outlet Height	ADA	36" MAX	36" MAX	36" MAX	36" MAX
	Measured	N/A			
Hallway Door Width	ADA	32" MIN			
Notes		NE Ramp	NW Ramp		

Courthouse Restrooms						
		Basen	nent	Fi	irst Floor	
		Unisex	Women	Men	Women	
Deer Orening	Measured	33"	33"	27"	33"	
Door Opening	ADA	32" N	/IN	32" MIN		
Stall Door	Measured	N/A	31.5"	24.5"	25.5"	
Stall Dool	ADA	32" N	/IN		32" MIN	
Stall/Bathroom	Measured	146"x136"	56"x38"	61"x32"	56"x36"	
Dimensions	ADA	56" DEEP X	60" WIDE	56" DI	EEP X 60" WIDE	
Grab Bars	Y/N	Y	Y	N/A	Υ	
Cuch Devilleicht	Measured	34"	34"	N/A	22"-39"(angled)	
Grab Bar Height	ADA	33" - 36"		33" - 36"		
Urinals	Y/N	Y	N/A	Y	N/A	
	Measured	19"	N/A	23"	N/A	
Urinal Height	ADA	17" MAX		17" MAX		
Tailat Caat Llaight	Measured	20"	20.5"	16"	16"	
Toilet Seat Height	ADA	17" - 19" MIN		17" - 19" MIN		
Counter/Sink	Measured	33.5"	32"	32"	32.5"	
Height	ADA	34" MAX		34" MAX		
	Measured	39"x19"	31"x2"	31"x2"	30.5"x2"	
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH		48" MAX HEIGHT, 20" MAX DEPTH		
	Measured	42"x11"	41"x20"	42"x20"	39.5"x20"	
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH		48" MAX HEIGHT, 20" MAX DEPTH		
Notes		Womens bath has an inside passage of 30.5"Women and mens bath inside passage of 30.5				

Courthouse Restrooms				
		Third	Floor	
		Men	Women	
DeerOpering	Measured	31"	33"	
Door Opening	ADA	32"	MIN	
Stall Door	Measured	24.5"	25.5"	
Stall Door	ADA	32"	MIN	
Stall/Bathroom	Measured	56"x33"	56"x36"	
Dimensions	ADA	56" DEEP 2	X 60" WIDE	
Grab Bars	Y/N	N/A	N/A	
Cash Devillatela	Measured	N/A	N/A	
Grab Bar Height	ADA	33"	- 36"	
Urinals	Y/N	Y	N/A	
11.2.5.111.2.6.1	Measured	22"	N/A	
Urinal Height	ADA	17"	MAX	
Tailat Cast Usight	Measured	16"	16"	
Toilet Seat Height	ADA	17" - 1	.9" MIN	
Countor/Cink Hoight	Measured	32"	32"	
Counter/Sink Height	ADA	34" MAX		
	Measured	31"x2"	31"x2"	
Towel/Dryer	ADA		IEIGHT, 20" DEPTH	
	Measured	41"x20"	43"x20"	
Soap	ADA		IEIGHT, 20" DEPTH	
Notes	has an insid	d mens bath e passage of 0.5"		

B. WHITE COUNTY BUILDING ANNEX - 110 N MAIN ST; MONTICELLO



Curb Ramp Near Annex



Street Parking



Entrance



Side Entrance



Front Entrance



Inner Entrance Door



Vestibule



Hallway



Unisex 1 Restroom



Unisex 1 Sink Area



Unisex 1 Toilet



Unisex 2 Restroom



Unisex 2 Restroom

Summary of Facility

For this study, the roadside parking, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

- No ADA Ramps at Accessible parking near entrance.
- Front Entrance Doors are less than minimum width.
- Grab bar in Unisex 1 Restroom exceeds ADA maximum height.
- Stall Dimensions in Unisex 2 Restroom are less than ADA requirements.
- No Grab bars in Unisex 2 Restroom

Annex Parking						
Stall Width	Measured	N/A				
	ADA	96" MIN				
	Measured	N/A				
Aisle Width	ADA	96" MIN				
Curb Ramp	Measured	N/A				
Width	ADA	48" MIN				
Curb Ramp	Measured	N/A				
Cross Slope	ADA	2% MAX				
Curb Ramp	Measured	N/A				
Running Slope	ADA	8.33% MAX				
No	street parking.					

Annex Building					
Ramp Running	Measured	N/A			
Slope	ADA	8.33% MAX			
Ramp Cross	Measured	N/A			
Slope	ADA	2% MAX			
Down Midth	Measured	N/A			
Ramp Width	ADA	36" MIN			
Ramp Handrails	Y/N	N			
Llowelwoil Lloight	Measured	N/A			
Handrail Height	ADA	34" - 38"			
Front Door	Measured	31" & 31"	32"(inner door)		
Front Door	ADA	32" MIN			
Fountain Spout	Measured	N/A			
Outlet Height	ADA	36" MAX			
Hallway Door	Measured	45"			
Width	ADA	32" MIN			
Notes: Ramp flush with sidewalk.		2 outer doo	rs and 1 inner.		

Annex Restrooms				
		Unisex 1	Unisex 2	
Door Opening	Measured	33"	25.5"	
	ADA	32"		
Stall Door	Measured	N/A	N/A	
	ADA	32"	MIN	
Stall/Bathroom	Measured	126"x92"	53"x52"	
Dimensions	ADA	56" DEEP >	(60" WIDE	
Grab Bars	Y/N	Y	N	
	Measured	38"		
Grab Bar Height	ADA	33" -	33" - 36"	
Urinals	Y/N	N	Ν	
	Measured	N/A	N/A	
Urinal Height	ADA	17" MAX		
	Measured	17.5"	17"	
Toilet Seat Height	ADA	17" - 19" MIN		
	Measured	33.5"	33.5"	
Counter/Sink Height	ADA	34" MAX		
	Measured	33.5"x20"	52.5"x20"	
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH		
	Measured	33.5"x18"	43"x16"	
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH		
Notes				

C. WHITE COUNTY SHERIFF'S DEPARTMENT/ JAIL 915 HANAWALT ST; MONTICELLO




Outer Entrance




Inner Entrance



Water Fountain



ADA Parking




ADA Aisle



Parking Curb Ramp




Men's Restroom Entrance



Men's Sink Area



Men's Toilet



Women's Restroom Entrance



Women's Sink Area



Women's Toilet

Summary of Facility

For this study, the parking lot, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

- Towel dispensers in the restrooms exceed the maximum ADA height.
- Soap dispensers in the restrooms exceed the maximum ADA height.

Sheriff's Dept/Jail - Parking Lot				
	Measured	102"		
Stall Width	ADA	96" MIN		
Aisle Width	Measured	102"		
	ADA	96" MIN		
Curb Ramp Width	Measured	N/A		
	ADA	48" MIN		
Curb Ramp Cross Slope	Measured	N/A		
	ADA	2% MAX		
Curb Ramp	Measured	N/A		
Running Slope	ADA	8.33% MAX		
No	tes			

Sheriff's Dept/Jail - Building				
Ramp Running Slope	Measured	N/A		
	ADA	8.33% MAX		
Ramp Cross Slope	Measured	N/A		
	ADA	2% MAX		
Ramp Width	Measured	N/A		
	ADA	36" MIN		
Ramp Handrails	Y/N	N/A		
Handrail Height	Measured	N/A		
	ADA	34" - 38"		
Front Door	Measured	36"		
Front Door	ADA	32" MIN		
Fountain	Measured	36"		
Spout Outlet Height	ADA	36" MAX		
Hallway Door Width	Measured	36"		
	ADA	32" MIN		
Not	tes			

Sheriff's Dept/Jail Lobby Restrooms				
		Men	Women	
Door Opening	Measured	36"	36"	
	ADA	32"	32" MIN	
Stall Door	Measured	N/A	N/A	
	ADA	32"	32" MIN	
Stall/Bathroom	Measured	N/A	N/A	
Dimensions	ADA	56" DEEP X 60" WIDE		
Grab Bars	Y/N	Y	Y	
	Measured	35"	35"	
Grab Bar Height	ADA	33"	33" - 36"	
Urinals	Y/N	N	N	
	Measured	N/A	N/A	
Urinal Height	ADA	17"	17" MAX	
Tailat Cast Haisht	Measured	19"	19"	
Toilet Seat Height	ADA	17" - 19" MIN		
Countor /Cink Hoight	Measured	34"	34"	
Counter/Sink Height	ADA	34"	34" MAX	
	Measured	52"	52"	
Towel/Dryer	ADA		48" MAX HEIGHT, 20" MAX DEPTH	
	Measured	52"	52"	
Soap	ADA		48" MAX HEIGHT, 20" MAX DEPTH	
Notes				

D. WHITE COUNTY HIGHWAY GARAGE – REYNOLDS, IN



ADA Parking



ADA Parking



ADA Parking



Parking Curb Ramp



Public Entrance



Ramp to Entrance



Entrance Door



Building Entry Area



Hallway



Water Fountain



Restroom Entrance



Restroom Toilet Area



Restroom Sink Area

.

For this study, the parking lot, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

Highway Garage - Parking Lot			
Stall Width	Measured	102"	
Stall Width	ADA	96" MIN	
Aiolo \A/idth	Measured	102"	
Aisle Width	ADA	96" MIN	
Curb Ramp	Measured	N/A	
Width	ADA	48" MIN	
Curb Ramp	Measured	N/A	
Cross Slope ADA		2% MAX	
Curb Ramp Measured		N/A	
Running Slope ADA		8.33% MAX	
No	tes		

Highway Garage - Building		
Ramp Running	Measured	3.25 and 3.90
Slope	ADA	8.33% MAX
Ramp Cross	Measured	.45 and .70
Slope	ADA	2% MAX
Domon Width	Measured	90" and 81"
Ramp Width	ADA	36" MIN
Ramp Handrails	Y/N	N
Handrail	Measured	N/A
Height	ADA	34" - 38"
Front Door	Measured	36"
Front Door	ADA	32" MIN
Fountain	Measured	39" and 36"
Spout Outlet Height	ADA	36" MAX
Hallway Door	Hallway Door Measured	
Width	ADA	32" MIN
Not	tes	

Highwa	estrooms			
		Unisex		
Deer Orening	Measured	36"		
Door Opening	ADA	32" MIN		
Stall Door	Measured	N/A		
Stall Door	ADA	32" MIN		
Stall/Bathroom	Measured	N/A		
Dimensions	ADA	56" DEEP X 60" WIDE		
Grab Bars	Y/N	Y		
Grab Bar	Measured	36"		
Height	ADA	33" - 36"		
Urinals	Y/N	N		
	Measured	N/A		
Urinal Height	ADA	17" MAX		
Toilet Seat	Measured	18"		
Height	ADA	17" - 19" MIN		
Counter/Sink	Measured	34"		
Height	ADA	34" MAX		
	Measured	40"		
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH		
	Measured	43"		
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH		
Not	es			

E. IVY TECH COMMUNITY COLLEGE MONTICELLO 1017 O CONNOR BLVD; MONTICELLO



ADA Parking



ADA Parking



ADA Parking



ADA Parking



Sidewalk



Front Entrance



Entrance



Inner Entrance



Restroom Area



Water Fountains



Men's Restroom Entrance




Men's Stall



Men's Stall Area







Men's Urinal Area



Men's Towel Dispensers



Women's Restroom Entrance



Women's Sink Area



Women's Towel Dispensers



Women's ADA Stall

For this study, the parking lot, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

Ivy Tech - Parking Lot			
Stall Width	Measured	120"	
	ADA	96" MIN	
Aido Midth	Measured	100"	
Aisle Width	ADA	96" MIN	
Curb Ramp	Measured	N/A	
Width	ADA	48" MIN	
Curb Ramp	Measured	N/A	
Cross Slope	ADA	2% MAX	
Curb Ramp	Measured	N/A	
Running Slope ADA		8.33% MAX	
Notes		Flat area leading from parking lot to building.	

Ivy Tech - Building			
Ramp Running	Measured	8.33%	
Slope	ADA	8.33% MAX	
Ramp Cross	Measured	0%	
Slope	ADA	2% MAX	
Domon Width	Measured	72"	
Ramp Width	ADA	36" MIN	
Ramp Handrails	Y/N	N/A	
Handrail	Measured	N/A	
Height	ADA	34" - 38"	
Front Door	Measured	42"	
Front Door	ADA	32" MIN	
Fountain	Measured	33"	
Spout Outlet Height ADA		36" MAX	
Hallway Door	Measured	N/A	
Width	ADA	32" MIN	
Not	tes		

Ivy Tech - Restrooms				
		Men	Women	
Deer Opening	Measured	48"	48"	
Door Opening	ADA	32"	MIN	
Stall Door	Measured	32.5"	32.5"	
Stall Door	ADA	32"	MIN	
Stall/Bathroom	Measured	59"x99"	59"x99"	
Dimensions	ADA	56" DEEP X	60" WIDE	
Grab Bars	Y/N	Y	Y	
Crah Dan Usisht	Measured	36"	36"	
Grab Bar Height	ADA	33" -	36"	
Urinals	Y/N	Y	N/A	
	Measured	15"	N/A	
Urinal Height	ADA	17" [MAX	
	Measured	18"	18"	
Toilet Seat Height	ADA	17" - 19	19" MIN	
	Measured	34"	34"	
Counter/Sink Height	ADA	34" 1	VAX	
	Measured	39"	39"	
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH		
	Measured	44" H, 16" D	44" H, 16" D	
Soap	ADA	48" MAX HEIG DEF		
Notes				

F. WHITE COUNTY HEALTH DEPARTMENT 902 FOXWOOD CT; MONTICELLO



Parking Lot



ADA Aisle to Curb Ramp



Curb Ramp from Parking



Entrance



Inner Entrance Door



Hallway



Unisex Restroom



Unisex Toilet Area



Unisex Sink Area



Staff Unisex Restroom



Staff Unisex Toilet Area



Staff Unisex Sink Area

For this study, the parking lot, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

Health Dept Parking Lot				
Stall Width	Measured	101"		
	ADA	96" MIN		
Aisle Width	Measured	102"		
Aisie width	ADA	96" MIN		
Curb Ramp	Measured	50"		
Width	ADA	48" MIN		
Curb Ramp	Measured	1.35%		
Cross Slope	ADA	2% MAX		
Curb Ramp	Curb Ramp Measured			
Running Slope ADA		8.33% MAX		
Notes				

Health Dept Building			
Ramp Running	Measured	0.51%	
Slope	ADA	8.33% MAX	
Ramp Cross	Measured	1.10%	
Slope	ADA	2% MAX	
Domo Width	Measured	71"	
Ramp Width	ADA	36" MIN	
Ramp Handrails	Y/N	N/A	
Llonduoil Lloight	Measured	N/A	
Handrail Height	ADA	34" - 38"	
Front Door	Measured	37"	
Front Door	ADA	32" MIN	
Fountain Spout	Measured	N/A	
Outlet Height ADA		36" MAX	
Hallway Door	Measured	33"	
Width	ADA	32" MIN	
Not	tes		

Health Dept Restrooms			
		Unisex	Staff
Door Opening	Measured	33"	33"
Door Opening	ADA	32"	MIN
Stall Door	Measured	N/A	N/A
Stall Dool	ADA	32"	MIN
Stall/Bathroom	Measured	89"x96"	81"x105"
Dimensions	ADA	56" DEEP	X 60" WIDE
Grab Bars	Y/N	Y	Y
Cuch Devide	Measured	34.5"	34"
Grab Bar Height	ADA	33"	- 36"
Urinals	Y/N	N/A	N/A
11.2.5.111.2.6.1	Measured	N/A	N/A
Urinal Height	ADA	17"	MAX
Tailat Coat Unight	Measured	18"	18"
Toilet Seat Height	ADA	17" - 1	l9" MIN
Countar/Sink Haight	Measured	34"	34"
Counter/Sink Height	ADA	34" MAX	
	Measured	40"x0"	39"x8"
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MA DEPTH	
	Measured	40"x19"	40"x6"
Soap	ADA	48" MAX HEIGHT, 20" M DEPTH	
Notes			

G. WHITE COUNTY AIRPORT – 2222 S AIRPORT RD; MONTICELLO



Parking Lot



Parking Lot Curb Ramp



Entrance



Water Fountain



Men's Restroom Door



Men's Restroom



Men's Sink Area



Men's Urinal Area



Men's Toilet



Women's Restroom Door



Women's Restroom



Women's Sink Area



Women's ADA Stall



Women's Typical Stall

For this study, the parking lot, curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

Airport Parking Lot				
Stall Width	Measured	104"		
	ADA	96" MIN		
Aisle Width	Measured	96"		
Alsie width	ADA	96" MIN		
Curle Derene Width	Measured	56"	60"	48"
Curb Ramp Width	ADA	48" MIN	48" MIN	48" MIN
Currh Darran Crease Claire	Measured	0.65%	0.0096	0.0068
Curb Ramp Cross Slope	ADA	2% MAX	2% MAX	2% MAX
Curk Dama Duraning Clana	Measured	3.60%	0.064	0.045
Curb Ramp Running Slope	ADA	8.33% MAX	8.33% MAX	8.33% MAX
Notes				

Airport Building				
Ramp Running	Measured	0.79%		
Slope	ADA	8.33% MAX		
Ramp Cross	Measured	0.78%		
Slope	ADA	2% MAX		
Donoro Miidth	Measured	64"		
Ramp Width	ADA	36" MIN		
Ramp Handrails	Y/N	Ν		
	Measured	N/A		
Handrail Height	ADA	34" - 38"		
Front Door	Measured	33"		
Front Door	ADA	32" MIN		
Fountain Spout	Measured	33"		
Outlet Height	ADA	36" MAX		
Hallway Door	Measured	N/A		
Width	ADA	32" MIN		
Not				

Airport Restrooms			
		Men	Women
Deer Opening	Measured	33"	33"
Door Opening	ADA	32" MIN	32" MIN
Stall Door	Measured	33.5"	33.5"
Stall Door	ADA	32" MIN	32" MIN
Stall/Bathroom -	Measured	95"x60"	97"x60"
Dimensions	ADA	56" DEEP X 60" WIDE	56" DEEP X 60" WIDE
Grab Bars	Y/N	Y	Y
Grab Bar	Measured	34.5"	34.5"
Height	ADA	33" - 36"	33" - 36"
Urinals	Y/N	Y	N
	Measured	15"	N/A
Urinal Height	ADA	17" MAX	17" MAX
Toilet Seat	Measured	18"	18"
Height	ADA	17" - 19" MIN	17" - 19" MIN
Counter/Sink	Measured	34"	34"
Height	ADA	34" MAX	34" MAX
	Measured	47"x0"	47"x0"
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH	48" MAX HEIGHT, 20" MAX DEPTH
	Measured	38"x17"	38"x17"
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH	48" MAX HEIGHT, 20" MAX DEPTH
Note	es		

H. WHITE COUNTY COMMUNITY CORRECTIONS 103B S MAIN ST; MONTICELLO



Street Parking



Entrance



Hallway Door



Men's Restroom Door



Men's Restroom



Women's Restroom Door



Women's Restroom

For this study curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

• Towel Dispenser or Hand Dryer in the Men's and Women's restroom exceeds the height and depth of ADA standards.

Community Corrrections Parking Lot			
Stall Width	Measured	N/A	
Stall Width	ADA	96" MIN	
Aisle Width	Measured	N/A	
	ADA	96" MIN	
Curb Ramp	Measured	N/A	
Width	ADA	48" MIN	
Curb Ramp	Measured	N/A	
Cross Slope	ADA	2% MAX	
Curb Ramp	Measured	N/A	
Running Slope	ADA	8.33% MAX	
Notes		Street Parking	

Community Corrrections Building			
Ramp Running	Measured	N/A	
Slope	ADA	8.33% MAX	
Ramp Cross	Measured	N/A	
Slope	ADA	2% MAX	
Damp Width	Measured	N/A	
Ramp Width	ADA	36" MIN	
Ramp Handrails	Y/N	N/A	
Llowdwoil Lloight	Measured	N/A	
Handrail Height	ADA	34" - 38"	
Front Door	Measured	34"	
Front Door	ADA	32" MIN	
Fountain Spout	Measured	N/A	
Outlet Height	ADA	36" MAX	
Hallway Door	Measured	33"	
Width	ADA	32" MIN	
Notes		Ramp flush with sidewalk	

Community Corrrections Restrooms			
		Men	Women
Deer Opening	Measured	35"	35"
Door Opening	ADA	32"	MIN
Stall Deer	Measured	N/A	N/A
Stall Door	ADA	32"	MIN
Stall/Bathroom	Measured	70"x60"	66"x60"
Dimensions	ADA	56" DEEP	X 60" WIDE
Grab Bars	Y/N	N/A	N/A
Cash Devillation	Measured	N/A	N/A
Grab Bar Height	ADA	33"	- 36"
Urinals	Y/N	N/A	N/A
	Measured	N/A	N/A
Urinal Height	ADA	17" MAX	
Tailat Cast Haisht	Measured	19"	19"
Toilet Seat Height	ADA	17" - 19" MIN	
Counter/Cicle Height	Measured	34.5"	34.5"
Counter/Sink Height	ADA	34" MAX	
	Measured	58"x28"	58"x28"
Towel/Dryer	ADA	48" MAX HEIGHT, 20"	
	AUA		DEPTH
	Measured	41"x14"	43"x14"
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH	
Notes			

I. WHITE COUNTY RENTAL PROPERTY 105 W BROADWAY ST; MONTICELLO



Street Parking




Entrance and Ramp



Hallway Door



Staff Unisex Restroom



Staff Unisex Sink Area



Staff Unisex Toilet Area

For this study curb ramps, access ramps, bathrooms and general door opening widths were measured and compared to the required PROWAG & ADAAG ADA standards. Listed below, and highlighted in the tables below, are the items mentioned that do not meet these ADA requirements.

ADA Non-Compliant Issues

- Door opening width to the Staff Restroom is less than the ADA requirements.
- Staff restroom is less than the ADA stall dimension requirements.

Rental Property Parking Lot			
Stall Width	Measured	N/A	
Stall Width	ADA	96" MIN	
Aisle Width	Measured	N/A	
	ADA	96" MIN	
Curb Ramp	Measured	N/A	
Width	ADA	48" MIN	
Curb Ramp	Measured	N/A	
Cross Slope	ADA	2% MAX	
Curb Ramp	Measured	N/A	
Running Slope	ADA	8.33% MAX	
Notes		Street parking	

Rental Property Building			
Ramp Running	Measured	8.15%	
Slope	ADA	8.33% MAX	
Ramp Cross	Measured	0.07%	
Slope	ADA	2% MAX	
Damp Width	Measured	79"	
Ramp Width	ADA	36" MIN	
Ramp Handrails	Y/N	N/A	
Llondroil Lloight	Measured	N/A	
Handrail Height	ADA	34" - 38"	
Front Door	Measured	34"	
Front Door	ADA	32" MIN	
Fountain Spout	Measured	N/A	
Outlet Height	ADA	36" MAX	
Hallway Door	Measured	N/A	
Width	ADA	32" MIN	
Notes			

Rental Property Restrooms			
		Staff	
Deer Opening	Measured	25.50"	
Door Opening	ADA	32" MIN	
Stall Door	Measured		
Stall Door	ADA	32" MIN	
Stall/Bathroom	Measured	76"x52"	
Dimensions	ADA	56" DEEP X 60" WIDE	
Grab Bars	Y/N	N/A	
Grab Bar	Measured	N/A	
Height	ADA	33" - 36"	
Urinals	Y/N	N/A	
	Measured	N/A	
Urinal Height	ADA	17" MAX	
Toilet Seat	Measured	17.50%	
Height	ADA	17" - 19" MIN	
Counter/Sink	Measured	32"	
Height	ADA	34" MAX	
	Measured	40"x5"	
Towel/Dryer	ADA	48" MAX HEIGHT, 20" MAX DEPTH	
	Measured	39"x18"	
Soap	ADA	48" MAX HEIGHT, 20" MAX DEPTH	
Note	es		

APPENDIX C: SIDEWALK AND CURB RAMP REVIEW

White County, through its hired consultant, completed a sidewalk and curb ramp review. The sidewalk and curb ramp locations are sorted by alphabetical order. The following describes White County's evaluation.

Sidewalks will be evaluated as follows:

- No Sidewalk
- Compliant
- Non-compliant, spot repairs needed (NC-Spot) (i.e. obstructions/defects that can be spot repaired)
- Non-compliant, full segment needs replaced (NC-Full) (non-compliant cross slope, running slope, condition, width, etc.)

Curb ramps will be evaluated as follows:

- Compliant
- Non-compliant but navigable (NC-Nav) (i.e. missing detectable warnings, non-compliant slopes, etc., but can be used by a wheelchair)
- Non-compliant, non-navigable (NC-Non-Nav) (sidewalk present)
- No curb ramp (no sidewalk present)

SIDEWALK EVALUATION					
STREET NAME	FROM	то	LEFT SIDEWALK	RIGHT SIDEWALK	
Francis St Bridge	Turbine Ct	NE Shafer Dr	Compliant	No Sidewalk	
Lowes Bridge Rd	East Shafer	Oakcrest Dr	Compliant	Compliant	
NW Shafer Dr	Rickey Rd	Norway Rd	No Sidewalk	Compliant	
NW Shafer Dr	Norway Rd	Highland Cove Ct	Highland Cove Ct No Sidewalk		
NW Shafer Dr	Highland Cove Ct	Untalulti Dr - South	No Sidewalk	Compliant	
NW Shafer Dr	Untalulti Dr - South	Hinshaw Dr	No Sidewalk	Compliant	
NW Shafer Dr	Hinshaw Dr	White Point Dr	No Sidewalk	Compliant	
NW Shafer Dr	White Point Dr	Untalulti Dr - North	No Sidewalk	Compliant	
NW Shafer Dr	Untalulti Dr - North	South Side of Bridge No Sidewalk		NC-Spot	
NW Shafer Dr	South Side of Bridge	Indiana Beach Rd	No Sidewalk	Compliant	
NW Shafer Dr	Harbour Ct	Indiana Beach Rd	No Sidewalk	Compliant	

CURB RAMP EVALUATION				
STREET INTERSECTION	NW CORNER	NE CORNER	SW CORNER	SE CORNER
Francis St Bridge/ NE Shafter Dr	Compliant	No Curb Ramp	No Curb Ramp	No Curb Ramp
Francis St Bridge/ West end of Bridge	Compliant	No Curb Ramp	No Curb Ramp	No Curb Ramp
Lowes Bridge Road/ East Shafer	NC-Non-Nav	NC-Non-Nav	No Curb Ramp	No Curb Ramp
Lowes Bridge Road/ Oakcrest Dr	No Curb Ramp	No Curb Ramp	NC-Non-Nav	NC-Non-Nav
NW Shafer Dr/ Harbour Ct	No Curb Ramp	No Curb Ramp	No Curb Ramp	No Curb Ramp
NW Shafer Dr/ Highland Cove Ct	No Curb Ramp	Compliant	No Curb Ramp	Compliant
NW Shafer Dr/ Hinshaw Dr	No Curb Ramp	No Curb Ramp	No Curb Ramp	No Curb Ramp
NW Shafer Dr/ Indiana Beach Rd	Compliant	Compliant	No Curb Ramp	Compliant
NW Shafer Dr/ Norway Rd	No Curb Ramp	Compliant	No Curb Ramp	Compliant
NW Shafer Dr/ Rickey Rd	No Curb Ramp	Compliant	No Curb Ramp	Compliant
NW Shafer Dr/ Untalulti Dr - North	No Curb Ramp	NC-Nav	No Curb Ramp	NC-Nav
NW Shafer Dr/ Untalulti Dr -South	No Curb Ramp	Compliant	No Curb Ramp	NC-Nav
NW Shafer Dr/ White Point Dr	No Curb Ramp	No Curb Ramp	No Curb Ramp	No Curb Ramp