

September 3, 2019

Arcelor Mittal USA, Inc.
250 W US Highway 12
Burns Harbor, IN 46304-9745

Work Order No.: 19I0034

Re: Daily

Dear Teri Kirk:

Microbac Laboratories, Inc. - Chicagoland Division received 22 sample(s) on 9/3/2019 10:20:00AM for the analyses presented in the following report as Work Order 19I0034.

The enclosed results were obtained from and are applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report have been reviewed and meet the applicable project specific and certification specific requirements, unless otherwise noted. A qualifications page is included in this report and lists the programs under which Microbac maintains certification.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories.

We appreciate the opportunity to service your analytical needs. If you have any questions, please contact your project manager. For any feedback, please contact Ron Misiunas, Division Manager, at ron.misiunas@microbac.com.

Sincerely,
Microbac Laboratories, Inc.



Carey Gadzala
Project Manager

WORK ORDER SAMPLE SUMMARY

Date: *Tuesday, September 3, 2019*

Client: Arcelor Mittal USA, Inc.
Project: Daily
Lab Order: 19I0034

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
19I0034-01	011-Composite	011	09/02/2019 06:00	9/3/2019 10:20:00AM
19I0034-02	011-Grab	011	09/02/2019 06:00	9/3/2019 10:20:00AM
19I0034-04	001-Composite	001	09/02/2019 06:20	9/3/2019 10:20:00AM
19I0034-05	001-Grab	001	09/02/2019 06:20	9/3/2019 10:20:00AM
19I0034-06	031-Grab	031	09/03/2019 06:31	9/3/2019 10:20:00AM
19I0034-07	Mixed Liquor-Grab	Mixed Liquor	09/03/2019 07:15	9/3/2019 10:20:00AM
19I0034-08	J-Box-Grab	J-Box	09/03/2019 06:29	9/3/2019 10:20:00AM
19I0034-09	WWII-Grab	WWII	09/03/2019 06:55	9/3/2019 10:20:00AM
19I0034-10	Coldwell-Grab	Coldwell	09/03/2019 07:15	9/3/2019 10:20:00AM
19I0034-11	RSB FT Overflow-Grab	RSB FT Overflow	09/03/2019 07:20	9/3/2019 10:20:00AM
19I0034-12	RSB FT Influent-Grab	RSB FT Influent	09/03/2019 07:21	9/3/2019 10:20:00AM
19I0034-13	BFTD-Grab	BFTD	09/03/2019 07:55	9/3/2019 10:20:00AM
19I0034-14	999-Grab	999	09/03/2019 07:45	9/3/2019 10:20:00AM
19I0034-15	BFTC-Grab	BFTC	09/03/2019 08:00	9/3/2019 10:20:00AM
19I0034-16	002-Grab	002	09/02/2019 08:11	9/3/2019 10:20:00AM
19I0034-17	WAL-Grab	WAL	09/02/2019 08:22	9/3/2019 10:20:00AM
19I0034-19	CM2-Grab	CM2	09/03/2019 00:00	9/3/2019 10:20:00AM
19I0034-20	CM6-Grab	CM6	09/03/2019 00:00	9/3/2019 10:20:00AM
19I0034-21	HM2-Grab	HM2	09/03/2019 00:00	9/3/2019 10:20:00AM
19I0034-22	HM3-Grab	HM3	09/03/2019 00:00	9/3/2019 10:20:00AM

Field Results

Date: *Tuesday, September 3, 2019*

Client: Arcelor Mittal USA, Inc.	Work Order: 19I0034
Client Project: Daily	
Client Sample ID: 011-Grab	Work Order/ID: 19I0034-02
Sample Description: 011	Sampled: 09/02/2019 06:00
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
FLD_CL_TITR	0.00	mg/L
pH	8.1	pH Units

Client Sample ID: 001-Grab	Work Order/ID: 19I0034-05
Sample Description: 001	Sampled: 09/02/2019 06:20
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
FLD_CL_TITR	0.00	mg/L
pH	7.9	pH Units

Client Sample ID: J-Box-Grab	Work Order/ID: 19I0034-08
Sample Description: J-Box	Sampled: 09/03/2019 06:29
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
pH	8.5	pH Units

Client Sample ID: RSB FT Overflow-Grab	Work Order/ID: 19I0034-11
Sample Description: RSB FT Overflow	Sampled: 09/03/2019 07:20
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
pH	11	pH Units

Client Sample ID: 999-Grab	Work Order/ID: 19I0034-14
Sample Description: 999	Sampled: 09/03/2019 07:45
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
pH	7.8	pH Units

Client Sample ID: 002-Grab	Work Order/ID: 19I0034-16
Sample Description: 002	Sampled: 09/02/2019 08:11
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
pH	8.1	pH Units

Client Sample ID: WAL-Grab	Work Order/ID: 19I0034-17
Sample Description: WAL	Sampled: 09/02/2019 08:22
Matrix: Aqueous	Received: 09/03/2019 10:20

Analyses	Result	Units
pH	9.1	pH Units

Field Results

Date: Tuesday, September 3, 2019

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-01
Client Project:	Daily	Sampled:	09/02/2019 6:00
Client Sample ID:	011-Composite	Received:	09/03/2019 10:20
Sample Description:	011		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: EPA 200.7 Rev 4.4				Analyst: RPL			
Prep Date/Time: 09/03/2019 10:52										
Total Recoverable Metals by ICP										
Lead	ejj	A	ND	0.0033	0.0075	U	mg/L	1	09/03/2019 13:54	
Zinc	ejj	A	0.015	0.0073	0.020	J	mg/L	1	09/03/2019 13:54	
			Method: SM 4500-CN C/E-1999				Analyst: ABG			
Prep Date/Time: 09/03/2019 11:15										
Total Cyanide										
Cyanide, Total	ejj	A	0.0042	0.0020	0.0050		mg/L	1	09/03/2019 14:09	
			Method: SW-846 9014				Analyst: ABG			
Prep Date/Time: 09/03/2019 10:40										
Free Cyanide										
Free Cyanide		A	ND		0.0062		mg/L	1	09/03/2019 13:45	
			Method: EPA 350.1 Rev 2.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Nitrogen, Ammonia as N										
Nitrogen, Ammonia (As N)	ei	A	0.24		0.10		mg/L	1	09/03/2019 13:08	
			Method: EPA 420.4 Rev 1.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Total Phenolics										
Phenolics, Total Recoverable	ejj	A	ND	0.0060	0.010	U	mg/L	1	09/03/2019 13:35	
			Method: SM 2540 D-1997				Analyst: KMT			
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids										
Total Suspended Solids	ejj	A	1.2	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-02
Client Project:	Daily	Sampled:	09/02/2019 6:00
Client Sample ID:	011-Grab	Received:	09/03/2019 10:20
Sample Description:	011		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: EPA 1664B				Analyst: KMT			
Oil & Grease (HEM) by SPE										
Prep Date/Time: 09/03/2019 10:43										
Oil & Grease (HEM)	ejj	A	2.0	1.4	5.0		mg/L	1	09/03/2019 14:43	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-04
Client Project:	Daily	Sampled:	09/02/2019 6:20
Client Sample ID:	001-Composite	Received:	09/03/2019 10:20
Sample Description:	001		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
			Method: EPA 200.7 Rev 4.4				Analyst: RPL		
Prep Date/Time: 09/03/2019 10:52									
Total Recoverable Metals by ICP									
Lead	ejj	A	ND	0.0033	0.0075	U	mg/L	1	09/03/2019 13:59
Zinc	ejj	A	0.010	0.0073	0.020	J	mg/L	1	09/03/2019 13:59
			Method: SM 4500-CN C/E-1999				Analyst: ABG		
Prep Date/Time: 09/03/2019 11:15									
Total Cyanide									
Cyanide, Total	ejj	A	0.0032	0.0020	0.0050		mg/L	1	09/03/2019 14:11
			Method: SW-846 9014				Analyst: ABG		
Prep Date/Time: 09/03/2019 10:40									
Free Cyanide									
Free Cyanide		A	ND		0.0062		mg/L	1	09/03/2019 13:47
			Method: EPA 350.1 Rev 2.0				Analyst: ABG		
Prep Date/Time: 09/03/2019 12:25									
Nitrogen, Ammonia as N									
Nitrogen, Ammonia (As N)	ei	A	0.30		0.10		mg/L	1	09/03/2019 13:15
			Method: EPA 420.4 Rev 1.0				Analyst: ABG		
Prep Date/Time: 09/03/2019 12:25									
Total Phenolics									
Phenolics, Total Recoverable	ejj	A	ND	0.0060	0.010	U	mg/L	1	09/03/2019 13:37
			Method: SM 2540 D-1997				Analyst: KMT		
Prep Date/Time: 09/03/2019 10:45									
Total Suspended Solids									
Total Suspended Solids	ejj	A	1.1	1.0	1.0		mg/L	1	09/03/2019 12:50

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-05
Client Project:	Daily	Sampled:	09/02/2019 6:20
Client Sample ID:	001-Grab	Received:	09/03/2019 10:20
Sample Description:	001		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: EPA 1664B				Analyst: KMT			
Prep Date/Time: 09/03/2019 10:43										
Oil & Grease (HEM) by SPE										
Oil & Grease (HEM)	ejj	A	3.3	1.4	5.0		mg/L	1	09/03/2019 14:43	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-06
Client Project:	Daily	Sampled:	09/03/2019 6:31
Client Sample ID:	031-Grab	Received:	09/03/2019 10:20
Sample Description:	031		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed		
			Method: SM 2540 D-1997				Analyst: KMT				
										Prep Date/Time: 09/03/2019 10:45	
Total Suspended Solids											
Total Suspended Solids	ejj	A	3.5	1.0	1.0		mg/L	1	09/03/2019 12:50		

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-07
Client Project:	Daily	Sampled:	09/03/2019 7:15
Client Sample ID:	Mixed Liquor-Grab	Received:	09/03/2019 10:20
Sample Description:	Mixed Liquor		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed
			Method: SM 2540 F-1997				Analyst: AMR		
			Prep Date/Time: 09/03/2019 10:50						
Settleable Solids									
Settleable Solids	i	A	190	1.0	1.0		ml/L	1	09/03/2019 11:50
			Method: SM 2540 D-1997				Analyst: KMT		
			Prep Date/Time: 09/03/2019 10:45						
Total Suspended Solids									
Total Suspended Solids	ejj	A	2200	1.0	1.0		mg/L	1	09/03/2019 12:50

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-08
Client Project:	Daily	Sampled:	09/03/2019 6:29
Client Sample ID:	J-Box-Grab	Received:	09/03/2019 10:20
Sample Description:	J-Box		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: EPA 350.1 Rev 2.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Nitrogen, Ammonia as N										
Nitrogen, Ammonia (As N)	ei	A	0.30		0.10		mg/L	1	09/03/2019 13:46	
			Method: EPA 420.4 Rev 1.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Total Phenolics										
Phenolics, Total Recoverable	ejj	A	ND	0.0060	0.010	U	mg/L	1	09/03/2019 13:38	
			Method: SM 2540 D-1997				Analyst: KMT			
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids										
Total Suspended Solids	ejj	A	10	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-09
Client Project:	Daily	Sampled:	09/03/2019 6:55
Client Sample ID:	WWII-Grab	Received:	09/03/2019 10:20
Sample Description:	WWII		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 4500-CN C/E-1999				Analyst: ABG			
			Prep Date/Time: 09/03/2019 11:15							
Total Cyanide										
Cyanide, Total	ejj	A	0.014	0.0020	0.0050		mg/L	1	09/03/2019 14:12	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-10
Client Project:	Daily	Sampled:	09/03/2019 7:15
Client Sample ID:	Coldwell-Grab	Received:	09/03/2019 10:20
Sample Description:	Coldwell		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 4500-CN C/E-1999				Analyst: ABG			
Prep Date/Time: 09/03/2019 11:15										
Total Cyanide										
Cyanide, Total	ejj	A	0.054	0.0020	0.0050		mg/L	1	09/03/2019 14:14	
			Method: EPA 350.1 Rev 2.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Nitrogen, Ammonia as N										
Nitrogen, Ammonia (As N)	ei	A	52			1.0	mg/L	1	09/03/2019 13:53	
			Method: SM 2540 D-1997				Analyst: KMT			
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids										
Total Suspended Solids	ejj	A	91	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: Tuesday, September 3, 2019

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-11
Client Project:	Daily	Sampled:	09/03/2019 7:20
Client Sample ID:	RSB FT Overflow-Grab	Received:	09/03/2019 10:20
Sample Description:	RSB FT Overflow		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: EPA 350.1 Rev 2.0				Analyst: ABG			
Prep Date/Time: 09/03/2019 12:25										
Nitrogen, Ammonia as N										
Nitrogen, Ammonia (As N)	ei	A	6.7		0.10		mg/L	1	09/03/2019 13:55	
			Method: SM 2540 D-1997				Analyst: KMT			
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids										
Total Suspended Solids	ejj	A	11	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-12
Client Project:	Daily	Sampled:	09/03/2019 7:21
Client Sample ID:	RSB FT Influent-Grab	Received:	09/03/2019 10:20
Sample Description:	RSB FT Influent		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed		
			Method: SM 2540 D-1997				Analyst: KMT				
										Prep Date/Time: 09/03/2019 10:45	
Total Suspended Solids											
Total Suspended Solids	ejj	A	1700	1.0	1.0		mg/L	1	09/03/2019 12:50		

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-13
Client Project:	Daily	Sampled:	09/03/2019 7:55
Client Sample ID:	BFTD-Grab	Received:	09/03/2019 10:20
Sample Description:	BFTD		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
Total Suspended Solids										
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids	ejj	A	55	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-14
Client Project:	Daily	Sampled:	09/03/2019 7:45
Client Sample ID:	999-Grab	Received:	09/03/2019 10:20
Sample Description:	999		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
			Prep Date/Time: 09/03/2019 10:45							
Total Suspended Solids										
Total Suspended Solids	ejj	A	1.8	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-15
Client Project:	Daily	Sampled:	09/03/2019 8:00
Client Sample ID:	BFTC-Grab	Received:	09/03/2019 10:20
Sample Description:	BFTC		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
Total Suspended Solids										
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids	ejj	A	39	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-19
Client Project:	Daily	Sampled:	09/03/2019 0:00
Client Sample ID:	CM2-Grab	Received:	09/03/2019 10:20
Sample Description:	CM2		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
Total Suspended Solids										
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids	ejj	A	14	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-20
Client Project:	Daily	Sampled:	09/03/2019 0:00
Client Sample ID:	CM6-Grab	Received:	09/03/2019 10:20
Sample Description:	CM6		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed		
			Method: SM 2540 D-1997				Analyst: KMT				
										Prep Date/Time: 09/03/2019 10:45	
Total Suspended Solids											
Total Suspended Solids	ejj	A	17	1.0	1.0		mg/L	1	09/03/2019 12:50		

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-21
Client Project:	Daily	Sampled:	09/03/2019 0:00
Client Sample ID:	HM2-Grab	Received:	09/03/2019 10:20
Sample Description:	HM2		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
Total Suspended Solids										
Prep Date/Time: 09/03/2019 10:45										
Total Suspended Solids	ejj	A	28	1.0	1.0		mg/L	1	09/03/2019 12:50	

Analytical Results

Date: *Tuesday, September 3, 2019*

Client:	Arcelor Mittal USA, Inc.	Work Order/ID:	19I0034-22
Client Project:	Daily	Sampled:	09/03/2019 0:00
Client Sample ID:	HM3-Grab	Received:	09/03/2019 10:20
Sample Description:	HM3		
Matrix:	Aqueous		

Analyses	Certs	AT	Result	MDL	RL	Qual	Units	DF	Analyzed	
			Method: SM 2540 D-1997				Analyst: KMT			
			Prep Date/Time: 09/03/2019 10:45							
Total Suspended Solids										
Total Suspended Solids	ejj	A	25	1.0	1.0		mg/L	1	09/03/2019 12:50	

ANALYTE TYPES: (AT)

A, B = Target Analyte

I = Internal Standard

M = Summation Analyte

S = Surrogate

T = Tentatively Identified Compound (TIC, concentration estimated)

**Partial**
9/3/2019

QC SAMPLE IDENTIFICATIONS

BLK = Method Blank

DUP = Method Duplicate

BS = Method Blank Spike

MS = Matrix Spike

ICB = Initial Calibration Blank

CCB = Continuing Calibration Blank

CRL = Client Required Reporting Limit

PDS = Post Digestion Spike

QCS = Quality Control Standard

ICSA = Interference Check Standard "A"

ICSAB = Interference Check Standard "AB"

BSD = Method Blank Spike Duplicate

MSD = Matrix Spike Duplicate

ICV = Initial Calibration Verification

CCV = Continuing Calibration Verification

OPR = Ongoing Precision and Recovery Standard

SD = Serial Dilution

CERTIFICATIONS (Certs)

Below is a list of certifications maintained by the Microbac Merrillville Laboratory. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. Complete lists of individual analytes pursuant to each certification below are available upon request.

d Illinois EPA drinking water, wastewater and solid waste analysis (#200064)

i Kansas Dept Health & Env. NELAP (#E-10397)

j Kentucky Wastewater Laboratory Certification Program (#108202)

FLAGS, FOOTNOTES AND ABBREVIATIONS (as needed)

J:	The result is an estimated quantity. The associated numerical value is the approximate concentration of the analyte in the sample.
MDL:	Minimum Detection Limit
RL:	Reporting Limit
RPD:	Relative Percent Difference
U:	The analyte was analyzed for but was not detected above the reported quantitation limit. The quantitation limit has been adjusted for any dilution or concentration of the sample.

Microbac Laboratories, Inc.

250 West 84th Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

Cooler Receipt Log

Cooler ID: Default Cooler



Partial

9/3/2019

Cooler Inspection Checklist

Ice Present or not required?	Yes
Shipping containers sealed or not required?	Yes
Custody seals intact or not required?	Yes
Chain of Custody (COC) Present?	Yes
COC includes customer information?	Yes
Relinquished and received signature on COC?	Yes
Sample collector identified on COC?	Yes
Sample type identified on COC?	Yes
Correct type of Containers Received	Yes
Correct number of containers listed on COC?	Yes
Containers Intact?	Yes
COC includes requested analyses?	Yes
Enough sample volume for indicated tests received?	Yes
Sample labels match COC (Name, Date & Time?)	Yes
Samples arrived within hold time?	Yes
Correct preservatives on COC or not required?	Yes
Chemical preservations checked or not required?	Yes
Preservation checks meet method requirements?	Yes
VOA vials have zero headspace, or not recd.?	Yes

Chain of Custody

ArcelorMittal Burns Harbor/Microbac Labs

Monday

Lab Work No: RT0034

* Date Obtained: 9-3-19
 ** Sample Date: 9-2-19

Location	Time	Sampler	Type	Preserved	Cooled	Containers			Parameters	Comments
						Type	Qty	Vol. (ml)		
011 **	<u>06:00</u>	<u>OP</u>	Comp	No	Yes	Glass	1	4000	NH3, TSS, Zn, Pb	01
			Grab	No	No	Plastic	1	500	pH, Tot Res Cl	02
			Grab	Yes	No	Glass	2	1000	FOG (prepreserved)	↓ 03 DWP
001 **	<u>06:20</u>		Comp	No	Yes	Glass	1	4000	NH3	04
			Grab	No	No	Plastic	1	125	pH	05
031 *	<u>06:31</u>		Grab	No	Yes	Plastic	1	1000	TSS	06
			Grab	No	No	Plastic	1	1000	BOD	↓
Mixed Liquor *	<u>07:15</u>		Grab	No	No	Plastic	1	2000	TSS, Settling	07
J-Box *	<u>06:29</u>		Grab	No	No	Glass	2	1000	NH3, Phenol, TSS, pH	08
DIW-131 *	<u>NA</u>		Grab	No	No	Plastic	1	125	pH	X
WWII *	<u>06:55</u>		Grab	No	No	Plastic	1	1000	Cn	09
Coldwell *	<u>07:15</u>		Grab	No	No	Plastic	2	2000	NH3, CN, Pb, Zn, TSS	10
RSB FT Overflow *	<u>07:20</u>		Grab	No	No	Plastic	2	1000	NH3, pH, TSS, Pb, Zn	11
RSB FT Influent *	<u>07:21</u>		Grab	No	No	Plastic	1	500	TSS	12
BFTD *	<u>07:55</u>		Grab	No	No	Plastic	1	500	TSS	13
999 *	<u>07:45</u>		Grab	No	No	Plastic	1	500	TSS, pH	14
BFTC *	<u>08:00</u>		Grab	No	No	Plastic	1	500	TSS	15
002 **	<u>08:11</u>		Grab	No	No	Plastic	1	125	pH	16
WAL 1 **	<u>08:22</u>		Grab	No	No	Glass	1	1000	TSS, pH	17
WAL 2 **	<u>NA</u>		Grab	No	No	Glass	1	1000	TSS, pH	X
WAL 3 **	<u>08:22</u>		Grab	No	No	Glass	1	1000	TSS, pH	X
SWTP *	<u>NA</u>	****	Grab	No	No	Plastic	<u>75</u>	1000	TSS	18-22

**** Sample collected by Water Process personnel

No CM 3 + HM 1

4.6
 - 0.3
4.3

Relinquished by: *C. Dula*
 Received by: *R2 - OAB*

Date: 9-3-19
 Date: 9/3/19

Time: 08:45
 Time: 0845

Env 1x Rev. 14 07/01/16 (TEK)



Microbac Laboratories - Chicagoland Division
pH - METHOD 9045D
Arcelor Mittal /Burns Harbor NPDES

Sample ID	pH		Analyst	Date/Time of Analysis
Buffer ID:	4: 185909	7: 188312	10: 191040	
Meter ID:			BAO	9/3/19 0800
Calibration	4 / 7 / 10			
ICV	4 / 7 / 10	7.00		
Slope		101.0		
Lake 999		7.77		
Location 001		7.91		
Location 002		8.10		
Location 011		8.05		
WAL 1		9.05		
WAL 2				
SWTP J-Box		8.49		
DIW 131				
RSB		10.98		
Dup- RSB		10.99		
CCV		7.01	↓	↓

Sample ID	pH		Analyst	Date/Time of Analysis
Buffer ID:	4:	7:	10:	
Meter ID:				
Calibration	4 / 7 / 10			
ICV	4 / 7 / 10			
Slope				
Lake 999				
Location 001				
Location 002				
Location 011				
WAL 1				
WAL 2				
SWTP J-Box				
DIW 131				
RSB				
Dup-				
CCV				

Microbac Laboratories, Inc. - Chicagoland Division
Residual Chlorine - METHOD SM 4500-Cl I-2000
Arcelor Mittal /Burns Harbor NPDES

Meter ID: DH meter Residual Chlorine Standard: A 9074
 Iodine Reagent: 146367 Acid Reagent: 147996

Sample ID	Residual Chlorine	Analyst	Date/Time of Analysis
Cal Std 1	0.02 mg/L	DAO	9/2/19 0810
Cal Std 2	0.05 mg/L		
Cal Std 3	0.1 mg/L		
Slope Blank	0.00		
LCS 0.02 mg/L	0.10		
011	0.00		
011 DUP	0.00		
001	0.00		
002	0.00		
003	0.00		
DUP 003	0.00		

Meter ID: DH meter Residual Chlorine Standard: A 9074
 Iodine Reagent: 146367 Acid Reagent: 147996

Sample ID	Residual Chlorine	Analyst	Date/Time of Analysis
Cal Std 1	0.02 mg/L	DAO	9/3/19 0800
Cal Std 2	0.05 mg/L		
Cal Std 3	0.1 mg/L		
Slope Blank	0.00		
LCS 0.02 mg/L	0.08		
011	0.00		
011 DUP	0.00		
001	0.00		
002	0.00		
003	0.00		
DUP 001	0.00		

Meter ID: _____ Residual Chlorine Standard: _____
 Iodine Reagent: _____ Acid Reagent: _____

Sample ID	Residual Chlorine	Analyst	Date/Time of Analysis
Cal Std 1	0.02 mg/L		
Cal Std 2	0.05 mg/L		
Cal Std 3	0.1 mg/L		
Slope			
LCS 0.02 mg/L			
011			
011 DUP			
001			
002			
003			
DUP			



ArcelorMittal

Burns Harbor

Contractor timesheet

Section 1

Date: 9/3/19 Shift: Day Contractor company name: Microbac Labs Contractor ref #/job #: _____ Form number: 309679

ArcelorMittal Representative: Warren Howard PO number: 0799897 Requisition number: 0799897

Department: END Description of work: water Samples Percent job complete: _____

Section 2

Badge no.	Last name	First name	Craft	ST	OT	DT	Total	Billable equipment/subcontractors/material	Job notes
<u>164042</u>	<u>Otto</u>	<u>Brian</u>	<u>TEC</u>	<u>1</u>			<u>1</u>	ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	
								ID Description Qty Hours/amt total	

Shift start time: _____ Shift end time: _____

Total hours this sheet: 1 Previous hours: _____ Total hours to date: 1

Is this job capital work? Yes No

Section 3 Enter the total hours worked by each craft in the box to the right of each abbreviation. See reverse side of form for an explanation of the abbreviations.

ABW	CL	EL	GLZ	JAN	LTR	PF	TEC
BL	CO	EN	INS	LA	MW	PT	TST
BM	CP	FN	IW	LIC	OE	SU	TM

Section 4

I the undersigned attest that the hours recorded on the timesheet were actually worked by the contractor employee at the plant work location on the date listed above.

Contractor authorization signature: [Signature] Job title: Service Tech

Printed name: P. Otto Date: 9/3/19

Contractor authorization signature: [Signature] Job title: Supervisor

Printed name: Warren Howard Date: 9/3/19

Section 5

Work authorization permit # 307289

Section 6

I the undersigned have verified that contractor employees, hours, and date listed on the timesheet are accurate, complete, valid for the date and plant work location listed above.

ArcelorMittal authorization signature: [Signature] Job title: Supervisor

Printed name: Warren Howard Date: 9/3/19

307289

Daily work authorization form for all visiting workers

For each job, and before starting work at the job site, a contractor representative must meet face to face with the ArcelorMittal representative responsible for the work and discuss the work to be performed and any specific safety requirements.



ArcelorMittal

Section 1

The named contractor or work crew is cleared to perform the job described herein:

Company name M.irobac Labs ArcelorMittal representative Warren Howard Date 9/3/19

Company contact/phone no Carey Gadzala 767-8378 ArcelorMittal representative department E-0 Cell 4863

Location and project/job description Enrico Bldg/water Samples ArcelorMittal representative phone number 4863 Clinic pickup point 46

Section 2

HIRAC-Lite	Yes	N/A	No	Yes	N/A	No
1) Are emergency evacuation areas identified and known?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
2) Is there a current and valid isolation (LOTO) procedure?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
3) Will everyone apply a personal safety lock?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
4) Are there adjacent work crews exposed (including ArcelorMittal employees)?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
5) Are there potential hazards or high risk job steps?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
6) Do we have the correct tools for the job?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
7) Is additional PPE required?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
8) Is there a potential for exposure (chemical, radiation, laser, temperature)?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
9) Is someone working on or near energized electrical equipment (motor control rooms, overhead power lines, etc.)?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
10) Could someone be caught in or between anything?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
11) Could someone get hurt as a result of a fall from height?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
12) Can something fall and/or strike me or someone else?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
13) Is everyone properly trained for this job?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
14) Are flags and details in place if needed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
15) Can we slip or trip on anything (including travel to and from the job)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
16) Have all affected people been notified?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
17) Can we strain or overexert ourselves?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
18) Has equipment been inspected prior to use? (tools, PPE, mobile equipment, etc.)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Other Hazards and Considerations for Discussion

	Yes	N/A	No	Yes	N/A	No	Yes	N/A	No
19) Pneumatic air tools & lines	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
20) Vehicle / mob equip traffic	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
21) Gas hazards-CO, CO2, etc.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
22) Hot process, metal, temp.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
23) Pressurized / steam pipe	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
24) Housekeeping	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
25) Production hazards	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
26) Material handling	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
27) Crane and rigging	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
28) Overhead work	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
29) Scaffold work	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
30) Explosives	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
31) Barricades	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
32) Radiation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
33) Asbestos	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
34) Noise	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
35) Lasers	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
36) Sewers	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Section 3

Visiting worker name (print) B. Otto

Badge # 164042

Hierarchy of Controls 1. Elimination 2. Substitution 3. Engineering 4. Administrative 5. PPE

Controls

Hazard #

Responsible Person

Hazard #

Responsible Person

Controls

Hazard #

Responsible Person

Hazard #

Responsible Person

Hazard #

Responsible Person

Hazard #

Responsible Person

15 Beware of uneven surfaces
17 Proper lifting at sawlers
20 vehicle movement

My crew and I are familiar with the safety hazards/considerations for this job. We are prepared to perform the work in a safe "workmanship" like manner. I have reviewed these considerations with the ArcelorMittal representative named below.

Contractor or crew leader B. Otto ArcelorMittal representative [Signature] Replacement rep/phone

(Ensure form is fully completed prior to signing) Original to contractor, (1) copy to ArcelorMittal representative Controlled by Maintenance Administration Dept. ArcelorMittal Buffalo Harbor

2016-04-BH-Daily Work Authorization